

**Request by Lamont-Doherty Earth Observatory for
an Incidental Harassment Authorization to Allow
the Incidental Take of Marine Mammals During a
Marine Seismic Survey in the Gulf of Alaska,
Late Summer/Early Autumn 2004**

submitted by

Lamont-Doherty Earth Observatory
61 Route 9W, P.O. Box 1000
Palisades, NY 10964-8000

to

National Marine Fisheries Service
Office of Protected Resources
1315 East-West Hwy, Silver Spring, MD 20910-3282

Application Prepared by

LGL Ltd., environmental research associates
22 Fisher St., POB 280, King City, Ont. L7B 1A6

12 April 2004

LGL Report TA2822-25

APPENDIX A:

REVIEW OF POTENTIAL IMPACTS OF AIRGUN SOUNDS ON MARINE MAMMALS⁴

The following subsections review relevant information concerning the potential effects of airgun sounds on marine mammals. This information is included here as background for the briefer summary of this topic included in § VII of the IHA Application. This background material is little changed from corresponding subsections included in IHA Applications and EAs submitted to NMFS during 2003 for other L-DEO projects. Those documents concerned L-DEO projects in the following areas: northern Gulf of Mexico, Hess Deep in the eastern tropical Pacific, Norway, Mid-Atlantic Ocean, Bermuda, Southeast Caribbean, and southern Gulf of Mexico (Yucatan Peninsula). Much of this information has also been included in varying formats in other reviews, assessments, and regulatory applications prepared by LGL Ltd., environmental research associates. Because this review is intended to be of general usefulness, it includes references to types of marine mammals that will not be found in some specific regions.

(a) Categories of Noise Effects

The effects of noise on marine mammals are highly variable, and can be categorized as follows (based on Richardson et al. 1995):

1. The noise may be too weak to be heard at the location of the animal, i.e., lower than the prevailing ambient noise level, the hearing threshold of the animal at relevant frequencies, or both;
2. The noise may be audible but not strong enough to elicit any overt behavioral response, i.e., the mammals may tolerate it;
3. The noise may elicit behavioral reactions of variable conspicuousness and variable relevance to the well being of the animal; these can range from subtle effects on respiration or other behaviors (detectable only by statistical analysis) to active avoidance reactions;
4. Upon repeated exposure, animals may exhibit diminishing responsiveness (habituation), or disturbance effects may persist; the latter is most likely with sounds that are highly variable in characteristics, unpredictable in occurrence, and associated with situations that the animal perceives as a threat;
5. Any man-made noise that is strong enough to be heard has the potential to reduce (mask) the ability of marine mammals to hear natural sounds at similar frequencies, including calls from conspecifics, echolocation sounds of odontocetes, and environmental sounds such as surf noise or (at high latitudes) ice noise. However, intermittent airgun or sonar pulses could cause masking for only a small proportion of the time, given the short duration of these pulses relative to the inter-pulse intervals;

⁴ By **W. John Richardson** and **Valerie D. Moulton**, LGL Ltd., environmental research associates. Revised November 2003.

6. Very strong sounds have the potential to cause temporary or permanent reduction in hearing sensitivity, or other physical effects. Received sound levels must far exceed the animal's hearing threshold for any temporary threshold shift to occur. Received levels must be even higher for a risk of permanent hearing impairment.

(b) Hearing Abilities of Marine Mammals

The hearing abilities of marine mammals are functions of the following (Richardson et al. 1995; Au et al. 2000):

1. Absolute hearing threshold at the frequency in question (the level of sound barely audible in the absence of ambient noise).
2. Critical ratio (the signal-to-noise ratio required to detect a sound at a specific frequency in the presence of background noise around that frequency).
3. The ability to localize sound direction at the frequencies under consideration.
4. The ability to discriminate among sounds of different frequencies and intensities.

Marine mammals rely heavily on the use of underwater sounds to communicate and to gain information about their surroundings. Experiments also show that they hear and may react to many man-made sounds including sounds made during seismic exploration.

Toothed Whales

Hearing abilities of some toothed whales (odontocetes) have been studied in detail (reviewed in Chapter 8 of Richardson et al. [1995] and in Au et al. [2000]). Hearing sensitivity of several species has been determined as a function of frequency. The small to moderate-sized toothed whales whose hearing has been studied have relatively poor hearing sensitivity at frequencies below 1 kHz, but extremely good sensitivity at, and above, several kHz. There are at present no specific data on the absolute hearing thresholds of most of the larger, deep-diving toothed whales, such as the sperm and beaked whales.

Despite the relatively poor sensitivity of small odontocetes at the low frequencies that contribute most of the energy in pulses of sound from airgun arrays, the sounds are sufficiently strong that their received levels sometimes remain above the hearing thresholds of odontocetes at distances out to several tens of kilometers (Richardson and Würsig 1997). However, there is no evidence that small odontocetes react to airgun pulses at such long distances, or even at intermediate distances where sound levels are well above the ambient noise level (see below).

The multibeam sonar operated from the *Ewing* emits pulsed sounds at 15.5 kHz. That frequency is within or near the range of best sensitivity of many odontocetes. Thus, sound pulses from the multibeam sonar will be readily audible to these animals when they are within the narrow angular extent of the transmitted sound beam.

Baleen Whales

The hearing abilities of baleen whales have not been studied directly. Behavioral and anatomical evidence indicates that they hear well at frequencies below 1 kHz (Richardson et al. 1995; Ketten 2000). Baleen whales also reacted to sonar sounds at 3.1 kHz and other sources centered at 4 kHz (see Richardson et al. 1995 for a review). Some baleen whales react to pinger sounds up to 28 kHz, but not to pingers or sonars emitting sounds at 36 kHz or above (Watkins 1986). In addition, baleen whales produce

sounds at frequencies up to 8 kHz and, for humpbacks, to >15 kHz (Au et al. 2001). The anatomy of the baleen whale inner ear seems to be well adapted for detection of low-frequency sounds (Ketten 1991, 1992, 1994, 2000). The absolute sound levels that they can detect below 1 kHz are probably limited by increasing levels of natural ambient noise at decreasing frequencies. Ambient noise energy is higher at low frequencies than at mid frequencies. At frequencies below 1 kHz, natural ambient levels tend to increase with decreasing frequency.

The hearing systems of baleen whales are almost certainly more sensitive to low-frequency sounds than are the ears of the small toothed whales. Thus, baleen whales are likely to hear airgun pulses farther away than can small toothed whales and, at closer distances, airgun sounds may seem more prominent to baleen than to toothed whales. However, baleen whales have commonly been seen well within the distances where seismic (or sonar) sounds would be detectable and yet often show no overt reaction to those sounds. Behavioral responses by baleen whales to seismic pulses have been documented, but received levels of pulsed sounds necessary to elicit behavioral reactions are typically well above the minimum detectable levels (Malme et al. 1984, 1988; Richardson et al. 1986, 1995; McCauley et al. 2000a; Johnson 2002).

Pinnipeds

Underwater audiograms have been obtained using behavioral methods for three species of phocinid seals, two species of monachid seals, two species of otariids, and the walrus (reviewed in Richardson et al. 1995: 211ff; Kastak and Schusterman 1998, 1999; Kastelein et al. 2002). In comparison with odontocetes, pinnipeds tend to have lower best frequencies, lower high-frequency cutoffs, higher auditory sensitivity at low frequencies, and poorer sensitivity at the best frequency.

At least some of the phocid (hair) seals have better sensitivity at low frequencies (≤ 1 kHz) than do odontocetes. Below 30–50 kHz, the hearing thresholds of most species tested are essentially flat down to about 1 kHz, and range between 60 and 85 dB re 1 μ Pa. Measurements for a harbor seal indicate that, below 1 kHz, its thresholds deteriorate gradually to ~ 97 dB re 1 μ Pa at 100 Hz (Kastak and Schusterman 1998). The northern elephant seal (not an Atlantic/Gulf of Mexico species) appears to have better underwater sensitivity than the harbor seal, at least at low frequencies (Kastak and Schusterman 1998, 1999).

For the otariid (eared) seals, the high frequency cutoff is lower than for phocinids, and sensitivity at low frequencies (e.g., 100 Hz) is poorer than for hair seals (harbor or elephant seal).

The underwater hearing of a walrus has recently been measured at frequencies from 125 Hz to 15 kHz (Kastelein et al. 2002). The range of best hearing was from 1–12 kHz, with maximum sensitivity (67 dB re 1 μ Pa) occurring at 12 kHz (Kastelein et al. 2002).

Sirenians

The hearing of manatees is sensitive at frequencies below 3 kHz. A West Indian manatee that was tested using behavioral methods could apparently detect sounds from 15 Hz to 46 kHz (Gerstein et al. 1999). Thus, manatees may hear, or at least detect, sounds in the low-frequency range where most seismic energy is released. It is possible that they are able to feel these low-frequency sounds using vibrotactile receptors or because of resonance in body cavities or bone conduction.

Based on measurements of evoked potentials, manatee hearing is apparently best around 1–1.5 kHz (Bullock et al. 1982). However, behavioral testing suggests their best sensitivity is at 6 to 20 kHz (Gerstein et al. 1999). The ability to detect high frequencies may be an adaptation to shallow water, where the propagation of low frequency sound is limited (Gerstein et al. 1999).

(c) Characteristics of Airgun Pulses

Airguns function by venting high-pressure air into the water. The pressure signature of an individual airgun consists of a sharp rise and then fall in pressure, followed by several positive and negative pressure excursions caused by oscillation of the resulting air bubble. The sizes, arrangement, and firing times of the individual airguns in an array are designed and synchronized to suppress the pressure oscillations subsequent to the first cycle. The resulting downward-directed pulse has a duration of only 10 to 20 ms, with only one strong positive and one strong negative peak pressure (Caldwell and Dragoset 2000). Most energy emitted from airguns is at relatively low frequencies. For example, typical high-energy airgun arrays emit most energy at 10–120 Hz. However, the pulses contain some energy up to 500–1000 Hz and above (Goold and Fish 1998). The pulsed sounds associated with seismic exploration have higher peak levels than other industrial sounds to which whales and other marine mammals are routinely exposed. The only sources with higher or comparable effective source levels are explosions.

The peak-to-peak source levels of the 2- to 20-airgun arrays used by L-DEO during various projects range from 236 to 263 dB re 1 μPa at 1 m, considering the frequency band up to about 250 Hz. These are the nominal source levels applicable to downward propagation. The effective source levels for horizontal propagation are lower. The only man-made sources with effective source levels as high as (or higher than) a large array of airguns are explosions and high-power sonars operating near maximum power.

Several important mitigating factors need to be kept in mind. (1) Airgun arrays produce intermittent sounds, involving emission of a strong sound pulse for a small fraction of a second followed by several seconds of near silence. In contrast, some other sources produce sounds with lower peak levels, but their sounds are continuous or discontinuous but continuing for much longer durations than seismic pulses. (2) Airgun arrays are designed to transmit strong sounds downward through the seafloor, and the amount of sound transmitted in near-horizontal directions is considerably reduced. Nonetheless, they also emit sounds that travel horizontally toward non-target areas. (3) An airgun array is a distributed source, not a point source. The nominal source level is an estimate of the sound that would be measured from a theoretical point source emitting the same total energy as the airgun array. That figure is useful in calculating the expected received levels in the far field, i.e., at moderate and long distances. Because the airgun array is not a single point source, there is no one location within the near field (or anywhere else) where the received level is as high as the nominal source level.

The strengths of airgun pulses can be measured in different ways, and it is important to know which method is being used when interpreting quoted source or received levels. Geophysicists usually quote peak-to-peak levels, in bar-meters or dB re 1 $\mu\text{Pa}\cdot\text{m}$. The peak (= zero-to-peak) level for the same pulse is typically about 6 dB less. In the biological literature, levels of received airgun pulses are often described based on the “average” or “root-mean-square” (rms) level over the duration of the pulse. The rms value for a given airgun pulse is typically about 10 dB lower than the peak level, and 16 dB lower than the peak-to-peak value (Greene 1997; McCauley et al. 1998, 2000a). A fourth measure that is sometimes used is the energy level, in dB re 1 $\mu\text{Pa}^2\cdot\text{s}$. Because the pulses are <1 s in duration, the numerical value of the energy is lower than the rms pressure level, but the units are different. Because the level of a given pulse will differ substantially depending on which of these measures is being applied, it is important to be aware which measure is in use when interpreting any quoted pulse level. In the past, NMFS has commonly referred to rms levels when discussing levels of pulsed sounds that might “harass” marine mammals.

Seismic sound received at any given point will arrive via a direct path, indirect paths that include reflection from the sea surface and bottom, and often indirect paths including segments through the

bottom sediments. Sounds propagating via indirect paths travel longer distances and often arrive later than sounds arriving via a direct path. (However, sound traveling in the bottom may travel faster than that in the water, and thus may, in some situations, arrive slightly earlier than the direct arrival despite traveling a greater distance.) These variations in travel time have the effect of lengthening the duration of the received pulse. Near the source, the predominant part of a seismic pulse is about 10 to 20 ms in duration. In comparison, the pulse duration as received at long horizontal distances can be much greater. For example, for one airgun array operating in the Beaufort Sea, pulse duration was about 300 ms at a distance of 8 km (4.3 n.mi.), 500 ms at 20 km (10.8 n.mi.), and 850 ms at 73 km or 39.4 n.mi. (Greene and Richardson 1988).

Another important aspect of sound propagation is that received levels of low-frequency underwater sounds diminish close to the surface because of pressure-release and interference phenomena that occur at and near the surface (Urick 1983; Richardson et al. 1995). Paired measurements of received airgun sounds at depths of 3 m (9.8 ft) vs. 9 m (29.5 ft) or 18 m (59 ft) have shown that received levels are typically several decibels lower at 3 m (Greene and Richardson 1988). For a mammal whose auditory organs are within 0.5 or 1 m (1.6–3.3 ft) of the surface, the received level of the predominant low-frequency components of the airgun pulses would be further reduced. In deep water, the received levels at deep depths can be considerably higher than those at relatively shallow (e.g., 18 m) depths and the same horizontal distance from the airguns (Tolstoy et al. 2004).

Pulses of underwater sound from open-water seismic exploration are often detected 50–100 km (27–54 n.mi.) from the source location, even during operations in nearshore waters (Greene and Richardson 1988; Burgess and Greene 1999). At those distances, the received levels are low—below 120 dB re 1 μ Pa on an approximate rms basis. However, faint seismic pulses are sometimes detectable at even greater ranges (e.g., Bowles et al. 1994; Fox et al. 2002). Considerably higher levels can occur at distances out to several kilometers from an operating airgun array.

(d) Masking Effects of Seismic Surveys

Masking effects of pulsed sounds on marine mammal calls and other natural sounds are expected to be limited, although there are few specific data on this. Some whales are known to continue calling in the presence of seismic pulses. Their calls can be heard between the seismic pulses (e.g., Richardson et al. 1986; McDonald et al. 1995; Greene et al. 1999). Although there has been one report that sperm whales cease calling when exposed to pulses from a very distant seismic ship (Bowles et al. 1994), a recent study reports that sperm whales off northern Norway continued calling in the presence of seismic pulses (Madsen et al. 2002). Masking effects of seismic pulses are expected to be negligible in the case of the smaller odontocete cetaceans, given the intermittent nature of seismic pulses plus the fact that sounds important to them are predominantly at much higher frequencies than are airgun sounds.

Most of the energy in the sound pulses emitted by airgun arrays is at low frequencies, with strongest spectrum levels below 200 Hz and considerably lower spectrum levels above 1000 Hz. These low frequencies are mainly used by mysticetes, but generally not by odontocetes, pinnipeds, or sirenians. An industrial sound source will reduce the effective communication or echolocation distance only if its frequency is close to that of the marine mammal signal. If little or no overlap occurs between the industrial noise and the frequencies used, as in the case of many marine mammals vs. airgun sounds, communication and echolocation are not expected to be disrupted. Furthermore, the discontinuous nature of seismic pulses makes significant masking effects unlikely even for mysticetes.

A few cetaceans are known to increase the source levels of their calls in the presence of elevated sound levels, or possibly to shift their peak frequencies in response to strong sound signals (Dahlheim 1987; Au 1993; Lesage et al. 1999; Terhune 1999; reviewed in Richardson et al. 1995:233ff, 364ff). These studies involved exposure to other types of anthropogenic sounds, not seismic pulses, and it is not known whether these types of responses ever occur upon exposure to seismic sounds. If so, these adaptations, along with directional hearing and preadaptation to tolerate some masking by natural sounds (Richardson et al. 1995), would all reduce the importance of masking.

(e) Disturbance by Seismic Surveys

Disturbance includes a variety of effects, including subtle changes in behavior, more conspicuous changes in activities, and displacement. In the terminology of the 1994 amendments to the MMPA, seismic noise could cause “Level B” harassment of certain marine mammals. Level B harassment is defined as “...disruption of behavioral patterns, including, but not limited to, migration, breathing, nursing, breeding, feeding, or sheltering.”

There has been debate regarding how substantial a change in behavior or mammal activity is required before the animal should be deemed to be “taken by Level B harassment”. NMFS has recently stated that

“...a simple change in a marine mammal’s actions does not always rise to the level of disruption of its behavioral patterns. ... If the only reaction to the [human] activity on the part of the marine mammal is within the normal repertoire of actions that are required to carry out that behavioral pattern, NMFS considers [the human] activity not to have caused a disruption of the behavioral pattern, provided the animal’s reaction is not otherwise significant enough to be considered disruptive due to length or severity. Therefore, for example, a short-term change in breathing rates or a somewhat shortened or lengthened dive sequence that are within the animal’s normal range and that do not have any biological significance (i.e., do not disrupt the animal’s overall behavioral pattern of breathing under the circumstances), do not rise to a level requiring a small take authorization.” (NMFS 2001, p. 9293).

Based on this guidance from NMFS, we assume that simple exposure to sound, or brief reactions that do not disrupt behavioral patterns in a potentially significant manner, do not constitute harassment or “taking”. By potentially significant, we mean “in a manner that might have deleterious effects to the well-being of individual marine mammals or their populations”.

Even with this guidance, there are difficulties in defining what marine mammals should be counted as “taken by harassment”. For many species and situations, we do not have detailed information about their reactions to noise, including reactions to seismic (and sonar) pulses. Behavioral reactions of marine mammals to sound are difficult to predict. Reactions to sound, if any, depend on species, state of maturity, experience, current activity, reproductive state, time of day, and many other factors. If a marine mammal does react to an underwater sound by changing its behavior or moving a small distance, the impacts of the change may not be significant to the individual let alone the stock or the species as a whole. However, if a sound source displaces marine mammals from an important feeding or breeding area for a prolonged period, impacts on the animals could be significant. Given the many uncertainties in predicting the quantity and types of impacts of noise on marine mammals, it is common practice to estimate how many mammals were present within a particular distance of industrial activities, or exposed to a particular level of industrial sound. This likely overestimates the numbers of marine mammals that are affected in some biologically important manner.

The definitions of “taking” in the U.S. Marine Mammal Protection Act, and its applicability to various activities, are presently (autumn 2003) under active consideration by the U.S. Congress. Some changes are likely. Also, the U.S. National Marine Fisheries Service is considering the adoption of new criteria concerning the noise exposures that are (and are not) expected to cause “takes” of various types. Thus, for projects subject to U.S. jurisdiction, changes in procedures may be required in the near future.

The sound criteria used to estimate how many marine mammals might be disturbed to some biologically-important degree by a seismic program are based on behavioral observations during studies of several species. However, information is lacking for many species. Detailed studies have been done on humpback, gray and bowhead whales, and on ringed seals. Less detailed data are available for some other species of baleen whales, sperm whales, and small toothed whales.

Baleen Whales

Baleen whales generally tend to avoid operating airguns, but avoidance radii are quite variable. Whales are often reported to show no overt reactions to airgun pulses at distances beyond a few kilometers, even though the airgun pulses remain well above ambient noise levels out to much longer distances. However, baleen whales exposed to strong noise pulses from airguns often react by deviating from their normal migration route and/or interrupting their feeding and moving away. Some of the main studies on this topic are the following: Malme et al. 1984, 1985, 1988; Richardson et al. 1986, 1995, 1999; Ljungblad et al. 1988; Richardson and Malme 1993; McCauley et al. 1998, 2000a; Miller et al. 1999.

Prior to the late 1990s, it was thought that bowhead whales, gray whales, and humpback whales all begin to show strong avoidance reactions to seismic pulses at received levels of about 160 to 170 dB re 1 μ Pa rms, but that subtle behavioral changes sometimes become evident at somewhat lower received levels. Recent studies have shown that some species of baleen whales (bowheads and humpbacks in particular) may show strong avoidance at received levels somewhat lower than 160–170 dB re 1 μ Pa rms. The observed avoidance reactions involved movement away from feeding locations or statistically significant deviations in the whales’ direction of swimming and/or migration corridor as they approached or passed the sound sources. In the case of the migrating whales, the observed changes in behavior appeared to be of little or no biological consequence to the animals—they simply avoided the sound source by displacing their migration route to varying degrees, but within the natural boundaries of the migration corridors.

Humpback Whales.—McCauley et al. (1998, 2000a) studied the responses of humpback whales off Western Australia to a full-scale seismic survey with a 16-airgun 2678-in³ array, and to a single 20 in³ airgun with source level 227 dB re 1 μ Pa·m (p-p). They found that the overall distribution of humpbacks migrating through their study area was unaffected by the full-scale seismic program. McCauley et al. (1998) did, however, document localized avoidance of the array and of the single gun. Avoidance reactions began at 5–8 km (2.7–4.3 n.mi.) from the array and those reactions kept most pods about 3–4 km (1.6–2.2 n.mi.) from the operating seismic boat. Observations were made from the seismic vessel, from which the maximum viewing distance was listed as 14 km (7.6 n.mi.). Avoidance distances with respect to the single airgun were smaller but consistent with the results from the full array in terms of the received sound levels. Mean avoidance distance from the airgun corresponded to a received sound level of 140 dB re 1 μ Pa rms; this was the level at which humpbacks started to show avoidance reactions to an approaching airgun. The standoff range, i.e., the closest point of approach of the airgun to the whales, corresponded to a received level of 143 dB rms. The initial avoidance response generally occurred at distances

of 5–8 km (2.7–4.3 n.mi.) from the airgun array and 2 km (1.1 n.mi.) from the single gun. However, some individual humpback whales, especially males, approached within distances 100–400 m (328–1312 ft), where the maximum received level was 179 dB re 1 μ Pa rms.

Humpback whales summering in southeast Alaska did not exhibit persistent avoidance when exposed to seismic pulses from a 1.64-L (100 in³) airgun (Malme et al. 1985). Some humpbacks seemed “startled” at received levels of 150–169 dB re 1 μ Pa. Malme et al. (1985) concluded that there was no clear evidence of avoidance, despite the possibility of subtle effects, at received levels up to 172 re 1 μ Pa on an approximate rms basis.

Bowhead Whales.—Bowhead whales on their summering grounds in the Canadian Beaufort Sea showed no obvious reactions to pulses from seismic vessels at distances of 6 to 99 km (3–53 n.mi.) and received sound levels of 107–158 dB on an approximate rms basis (Richardson et al. 1986); their general activities were indistinguishable from those of a control group. However, subtle but statistically significant changes in surfacing–respiration–dive cycles were evident upon statistical analysis. Bowheads usually did show strong avoidance responses when seismic vessels approached within a few kilometers (~3–7 km or 1.6–3.8 n.mi.) and when received levels of airgun sounds were 152–178 dB (Richardson et al. 1986, 1995; Ljungblad et al. 1988). In one case, bowheads engaged in near-bottom feeding began to turn away from a 30-airgun array with a source level of 248 dB re 1 μ Pa·m at a distance of 7.5 km (4 n.mi.), and swam away when it came within about 2 km (1.1 n.mi.). Some whales continued feeding until the vessel was 3 km (1.6 n.mi.) away. Feeding bowhead whales tend to tolerate higher sound levels than migrating whales before showing an overt change in behavior. The feeding whales may be affected by the sounds, but the need to feed may reduce the tendency to move away.

Migrating bowhead whales in the Alaskan Beaufort Sea seem more responsive to noise pulses from a distant seismic vessel than are summering bowheads. In 1996–98, a partially-controlled study of the effect of Ocean Bottom Cable (OBC) seismic surveys on westward-migrating bowheads was conducted in late summer and autumn in the Alaskan Beaufort Sea (Miller et al. 1999; Richardson et al. 1999). Aerial surveys showed that some westward-migrating whales avoided an active seismic survey boat by 20–30 km (10.8–16.2 n.mi.), and that few bowheads approached within 20 km (10.8 n.mi.). Received sound levels at those distances were only 116–135 dB re 1 μ Pa (rms). Some whales apparently began to deflect their migration path when still as much as 35 km (19 n.mi.) away from the airguns. At times when the airguns were not active, many bowheads moved into the area close to the inactive seismic vessel. Avoidance of the area of seismic operations did not persist beyond 12–24 h after seismic shooting stopped. These and other data suggest that migrating bowhead whales are more responsive to seismic pulses than were summering bowheads.

Gray Whales.—Malme et al. (1986, 1988) studied the responses of feeding gray whales to pulses from a single 100 in³ airgun off St. Lawrence Island in the northern Bering Sea. They estimated, based on small sample sizes, that 50% of feeding gray whales ceased feeding at an average received pressure level of 173 dB re 1 μ Pa on an (approximate) rms basis, and that 10% of feeding whales interrupted feeding at received levels of 163 dB. Malme et al. (1986) estimated that an average pressure level of 173 dB occurred at a range of 2.6 to 2.8 km (1.4–1.5 n.mi.) from an airgun array with a source level of 250 dB (0-pk) in the northern Bering Sea. These findings were generally consistent with the results of experiments conducted on larger numbers of gray whales that were migrating along the California coast. Malme and Miles (1985) concluded that, during migration, changes in swimming pattern occurred for received levels of about 160 dB re 1 μ Pa and higher, on an approximate rms basis. The 50% probability of avoidance was estimated to occur at a CPA distance of 2.5 km (1.3 n.mi.) from a 4000-in³ array operating off central

California (CPA = closest point of approach). This would occur at an average received sound level of about 170 dB (rms). Some slight behavioral changes were noted at received sound levels of 140 to 160 dB (rms).

There was no indication that Western gray whales exposed to seismic noise were displaced from their overall feeding grounds near Sakhalin Island during seismic programs in 1997 (Würsig et al. 1999) and in 2001. However, there were indications of subtle behavioral effects and (in 2001) localized avoidance by some individuals (Johnson 2002; Weller et al. 2002).

Rorquals.—Blue, sei, fin, and minke whales have occasionally been reported in areas ensonified by airgun pulses. Sightings by observers on seismic vessels off the U.K. from 1997 to 2000 suggest that, at times of good sightability, numbers of rorquals seen are similar when airguns are shooting and not shooting (Stone 2003). Although individual species did not show any significant displacement in relation to seismic activity, all baleen whales combined were found to remain significantly further from the airguns during shooting compared with periods without shooting (Stone 2003). Baleen whale pods sighted from the ship were found to be at a median distance of about 1.6 km (0.9 n.mi.) from the array during shooting and 1.0 km (0.5 n.mi.) during periods without shooting (Stone 2003). Baleen whales, as a group, made more frequent alterations of course (usually away from the vessel) during shooting compared with periods of no shooting (Stone 2003). In addition, fin/sei whales were less likely to remain submerged during periods of seismic shooting (Stone 2003).

Discussion and Conclusions.—Baleen whales generally tend to avoid operating airguns, but avoidance radii are quite variable. Whales are often reported to show no overt reactions to airgun pulses at distances beyond a few kilometers, even though the airgun pulses remain well above ambient noise levels out to much longer distances. However, recent studies of humpback and especially migrating bowhead whales show that reactions, including avoidance, sometimes extend to greater distances than documented earlier. Avoidance distances often exceed the distances at which boat-based observers can see whales, so observations from the source vessel are biased.

Some baleen whales show considerable tolerance of seismic pulses. However, when the pulses are strong enough, avoidance or other behavioral changes become evident. Because the responses become less obvious with diminishing received sound level, it has been difficult to determine the maximum distance (or minimum received sound level) at which reactions to seismic become evident and, hence, how many whales are affected.

Studies of gray, bowhead, and humpback whales have determined that received levels of pulses in the 160–170 dB re 1 μ Pa rms range seem to cause obvious avoidance behavior in a substantial fraction of the animals exposed. In many areas, seismic pulses diminish to these levels at distances ranging from 4.5 to 14.5 km (2.4–7.8 n.mi.) from the source. A substantial proportion of the baleen whales within this distance range may show avoidance or other strong disturbance reactions to the seismic array.

Data on short-term reactions (or lack of reactions) of cetaceans to impulsive noises do not necessarily provide information about long-term effects. It is not known whether impulsive noises affect reproductive rate or distribution and habitat use in subsequent days or years. Gray whales continued to migrate annually along the west coast of North America despite intermittent seismic exploration (and much ship traffic) in that area for decades (Appendix A in Malme et al. 1984). Bowhead whales continued to travel to the eastern Beaufort Sea each summer despite seismic exploration in their summer and autumn range for many years. Bowheads were often seen in summering areas where seismic exploration occurred in preceding summers (Richardson et al. 1987). They also have been observed over periods of days or weeks in areas repeatedly ensonified by seismic pulses. However, it is not known whether the same individual bowheads were

involved in these repeated observations (within and between years) in strongly ensonified areas. It is also not known whether whales that tolerate exposure to seismic pulses are stressed.

Toothed Whales

Little systematic information is available about reactions of toothed whales to noise pulses. Few studies similar to the more extensive baleen whale/seismic pulse work summarized above have been reported for toothed whales, and none similar in size and scope to the studies of humpback, bowhead and gray whales mentioned above. However, systematic work on sperm whales is underway.

Delphinids and Similar Species.—Seismic operators sometimes see dolphins and other small toothed whales near operating airgun arrays, but in general there seems to be a tendency for most delphinids to show some limited avoidance of operating seismic vessels. Authors reporting cases of small toothed whales close to the operating airguns have included Duncan (1985), Arnold (1996), and Stone (2003). When a 3959 in³, 18-airgun array was firing off California, toothed whales behaved in a manner similar to that observed when the airguns were silent (Arnold 1996). Most, but not all, dolphins often seemed to be attracted to the seismic vessel and floats, and some rode the bow wave of the seismic vessel regardless of whether the guns were firing. However, in Puget Sound, Dall's porpoises observed when a 6000 in³, 12–16-airgun array was firing tended to be heading away from the boat (Calambokidis and Osmek 1998).

Goold (1996a,b,c) studied the effects on common dolphins, *Delphinus delphis*, of 2D seismic surveys in the Irish Sea. Passive acoustic surveys were conducted from the "guard ship" that towed a hydrophone 180-m aft. The results indicated that there was a local displacement of dolphins around the seismic operation. However, observations indicated that the animals were tolerant of the sounds at distances outside a 1-km (0.5 n.mi.) radius from the guns (Goold 1996a). Initial reports of larger-scale displacement were later shown to represent a normal autumn migration of dolphins through the area, and were not attributable to seismic surveys (Goold 1996a,b,c).

Observers stationed on seismic vessels operating off the United Kingdom from 1997–2000 have provided data on the occurrence and behavior of various toothed whales exposed to seismic pulses (Stone 2003). Dolphins of various species often showed more evidence of avoidance of operating airgun arrays than has been reported previously for small odontocetes. Sighting rates of white-sided dolphins, white-beaked dolphins, *Lagenorhynchus* spp., and all small odontocetes combined were significantly lower during periods of shooting. Except for pilot whales, all of the small odontocete species tested, including killer whales, were found to be significantly farther from large airgun arrays during periods of shooting compared with periods of no shooting. Pilot whales showed few reactions to seismic activity. The displacement of the median distance from the array was ~0.5 km (0.3 n.mi.) or more for most species groups. Killer whales also appear to be more tolerant of seismic shooting in deeper waters.

For all small odontocete species, except pilot whales, that were sighted during seismic surveys off the United Kingdom in 1997–2000, the numbers of positive interactions with the survey vessel (e.g., bow-riding, approaching the vessel, etc.) were significantly fewer during periods of shooting. All small odontocetes combined showed more negative interactions (e.g., avoidance) during periods of shooting. Small odontocetes, including white-beaked dolphins, *Lagenorhynchus* spp., and other dolphin spp. showed a tendency to swim faster during periods with seismic shooting; *Lagenorhynchus* spp. were also observed to swim more slowly during periods without shooting. Significantly fewer white-beaked dolphins, *Lagenorhynchus* spp., harbor porpoises, and pilot whales traveled towards the vessel and/or more were traveling away from the vessel during periods of shooting.

Captive bottlenose dolphins and beluga whales exhibit changes in behavior when exposed to strong pulsed sounds similar in duration to those typically used in seismic surveys (Finneran et al. 2000, 2002). Finneran et al. (2002) exposed a captive bottlenose dolphin and white whale to single impulses from a watergun (80 in³). As compared with airgun pulses, water gun impulses were expected to contain proportionally more energy at higher frequencies because there is no significant gas-filled bubble, and thus little low-frequency bubble-pulse energy (Hutchinson and Detrick 1984). The captive animals sometimes vocalized after exposure and exhibited a reluctance to station at the test site where subsequent exposure to impulses would be implemented (Finneran et al. 2002). Similar behaviors were exhibited by captive bottlenose dolphins and a white whale exposed to single underwater pulses designed to simulate those produced by distant underwater explosions (Finneran et al. 2000). It is uncertain what relevance these observed behaviors in captive, trained marine mammals exposed to single sound pulses may have to free-ranging animals exposed to multiple pulses. In any event, the animals tolerated rather high received levels of sound (pk-pk level >200 dB re 1 μ Pa) before exhibiting the aversive behaviors mentioned above.

Observations of odontocete responses (or lack of responses) to noise pulses from underwater explosions (as opposed to airgun pulses) may be relevant as an indicator of odontocete responses to very strong noise pulses. During the 1950s, small explosive charges were dropped into an Alaskan river in attempts to scare belugas away from salmon. Success was limited (Fish and Vania 1971; Frost et al. 1984). Small explosive charges were “not always effective” in moving bottlenose dolphins away from sites in the Gulf of Mexico where larger demolition blasts were about to occur (Klima et al. 1988). Odontocetes may be attracted to fish killed by explosions, and thus attracted rather than repelled by “scare” charges. Captive false killer whales showed no obvious reaction to single noise pulses from small (10 g) charges; the received level was ~185 dB re 1 μ Pa (Akamatsu et al. 1993). Jefferson and Curry (1994) reviewed several additional studies that found limited or no effects of noise pulses from small explosive charges on killer whales and other odontocetes. Aside from the potential for TTS, the tolerance to these charges may indicate a lack of effect or the failure to move away may simply indicate a stronger desire to eat, regardless of circumstances.

Beaked Whales.—There are no specific data on the behavioral reactions of beaked whales to seismic surveys. Most beaked whales tend to avoid approaching vessels of other types (e.g., Würsig et al. 1998). They may also dive for an extended period when approached by a vessel (e.g., Kasuya 1986). It is likely that these beaked whales would normally show strong avoidance of an approaching seismic vessel, but this has not been documented explicitly. Northern bottlenose whales sometimes are quite tolerant of slow-moving vessels (Reeves et al. 1993; Hooker et al. 2001). However, those vessels were not emitting airgun pulses.

There are increasing indications that some beaked whales tend to strand when naval exercises, including sonar operation, are ongoing nearby (e.g., Simmonds and Lopez-Jurado 1991; Frantzis 1998; NOAA and USN 2001; Jepson et al. 2003; see also the “Strandings and Mortality” subsection, later). These strandings are apparently at least in part a disturbance response, although auditory or other injuries may also be a factor. Whether beaked whales would ever react similarly to seismic surveys is unknown. Seismic survey sounds are quite different from those of the sonars in operation during the above-cited incidents. There has been a recent (Sept. 2002) stranding of Cuvier’s beaked whales in the Gulf of California (Mexico) when the L-DEO vessel *Maurice Ewing* was conducting a seismic survey in the general area (e.g., Malakoff 2002). Another stranding of Cuvier’s beaked whales in the Galapagos occurred during a seismic survey in April 2000; however “There is no obvious mechanism that bridges the distance between this source and the stranding site” (Gentry 2002). The evidence with respect to seismic surveys and beaked whale strandings is inconclusive, and NMFS has not established a link between the Gulf of California stranding and the seismic activities (Hogarth 2002).

Sperm Whales.—All three species of sperm whales have been reported to show avoidance reactions to standard vessels not emitting airgun sounds (e.g., Richardson et al. 1995; Würsig et al. 1998). Thus, it is to be expected that they would tend to avoid an operating seismic survey vessel. There are some limited observations suggesting that sperm whales in the Southern Ocean ceased calling during some (but not all) times when exposed to weak noise pulses from extremely distant (>300 km or 162 n.mi.) seismic exploration (Bowles et al. 1994). This “quieting” was suspected to represent a disturbance effect, in part because sperm whales exposed to pulsed man-made sounds at higher frequencies often cease calling (Watkins and Schevill 1975; Watkins et al. 1985). Also, sperm whales in the Gulf of Mexico may have moved away from a seismic vessel (Mate et al. 1994).

On the other hand, recent (and more extensive) data from vessel-based monitoring programs in U.K. waters suggest that sperm whales in that area show little evidence of avoidance or behavioral disruption in the presence of operating seismic vessels (Stone 2003). These types of observations are difficult to interpret because the observers are stationed on or near the seismic vessel, and may underestimate reactions by some of the more responsive species or individuals, which may be beyond visual range. However, the U.K. results do seem to show considerable tolerance of seismic surveys by at least some sperm whales. Also, a recent study off northern Norway indicated that sperm whales continued to call when exposed to pulses from a distant seismic vessel. Received levels of the seismic pulses were up to 146 dB re 1 μ Pa pk-pk (Madsen et al. 2002). Similarly, a study conducted off Nova Scotia that analyzed recordings of sperm whale vocalizations at various distances from an active seismic program did not detect any obvious changes in the distribution or behavior of sperm whales (McCall Howard 1999). An experimental study of sperm whale reactions to seismic surveys in the Gulf of Mexico is presently underway (Caldwell 2002; Jochens and Biggs 2003), along with a study of the movements of sperm whales with satellite-linked tags in relation to seismic surveys (Mate 2003). During two controlled exposure experiments where sperm whales were exposed to seismic pulses at received levels up to 148 dB re 1 μ Pa, there was no indication of avoidance of the vessel or changes in feeding efficiency (Jochens and Biggs 2003). The received sounds were measured on an “rms over octave band with most energy” basis (P. Tyack, pers. comm. to LGL Ltd.); the broadband rms value would be somewhat higher. Although the sample size from the initial work was small (four whales during two experiments), the results are consistent with those off northern Norway.

Conclusions.—Dolphins and porpoises are often seen by observers on active seismic vessels, occasionally at close distances (e.g., bow riding). However, some studies, especially near the U.K., show localized avoidance. In contrast, recent studies show little evidence of reactions by sperm whales to airgun pulses, contrary to earlier indications.

There are no specific data on responses of beaked whales to seismic surveys, but it is likely that most if not all species show strong avoidance. There is increasing evidence that some beaked whales may strand after exposure to strong noise from sonars. Whether they ever do so in response to seismic survey noise is unknown.

Pinnipeds

Few studies of the reactions of pinnipeds to noise from open-water seismic exploration have been published (for review, see Richardson et al. 1995). However, pinnipeds have been observed during a number of seismic monitoring studies in recent years. Monitoring studies in the Beaufort Sea during 1996–2001 provide a substantial amount of information on avoidance responses (or lack thereof) and associated behavior. Pinnipeds exposed to seismic surveys have also been observed during recent seismic

surveys along the USWW. Some limited data are available on physiological responses of seals exposed to seismic sound, as studied with the aid of radio telemetry. Also, there are data on the reactions of pinnipeds to various other related types of impulsive sounds.

Early observations provided considerable evidence that pinnipeds are often quite tolerant of strong pulsed sounds. During seismic exploration off Nova Scotia, grey seals exposed to noise from airguns and linear explosive charges reportedly did not react strongly (J. Parsons *in* Greene et al. 1985). An airgun caused an initial startle reaction among South African fur seals but was ineffective in scaring them away from fishing gear (Anonymous 1975). Pinnipeds in both water and air sometimes tolerate strong noise pulses from non-explosive and explosive scaring devices, especially if attracted to the area for feeding or reproduction (Mate and Harvey 1987; Reeves et al. 1996). Thus, pinnipeds are expected to be rather tolerant of, or habituate to, repeated underwater sounds from distant seismic sources, at least when the animals are strongly attracted to the area.

In the United Kingdom, a radio-telemetry study has demonstrated short-term changes in the behavior of harbor (=common) seals and grey seals exposed to airgun pulses (Thompson et al. 1998). In this study, harbor seals were exposed to seismic pulses from a 90 in³ array (3 × 30 in³ airguns), and behavioral responses differed among individuals. One harbor seal avoided the array at distances up to 2.5 km (1.3 n.mi.) from the source and only resumed foraging dives after seismic stopped. Another harbor seal exposed to the same small airgun array showed no detectable behavioral response, even when the array was within 500 m (1641 ft). All grey seals exposed to a single 10 in³ airgun showed an avoidance reaction. Seals moved away from the source, increased swim speed and/or dive duration, and switched from foraging dives to predominantly transit dives. These effects appeared to be short-term as all grey seals either remained in, or returned at least once to, the foraging area where they had been exposed to seismic pulses. These results suggest that there are interspecific as well as individual differences in seal responses to seismic sounds.

Off California, visual observations from a seismic vessel showed that California sea lions “typically ignored the vessel and array. When [they] displayed behavior modifications, they often appeared to be reacting visually to the sight of the towed array. At times, California sea lions were attracted to the array, even when it was on. At other times, these animals would appear to be actively avoiding the vessel and array.” (Arnold 1996). In Puget Sound, sighting distances for harbor seals and California sea lions tended to be larger when airguns were operating; both species tended to orient away whether or not the airguns were firing (Calambokidis and Osmek 1998).

Monitoring work in the Alaskan Beaufort Sea during 1996–2001 provided considerable information regarding the behavior of seals exposed to seismic pulses (Harris et al. 2001; Moulton and Lawson 2002). These seismic projects usually involved arrays of 6 to 16 airguns with total volumes 560 to 1500 in³. The combined results suggest that some seals avoid the immediate area around seismic vessels. In most survey years, ringed seal sightings tended to be farther away from the seismic vessel when the airguns were operating than when they were not (Moulton and Lawson 2002). However, these avoidance movements were relatively small, on the order of 100 m (328 ft) to (at most) a few hundreds of meters, and many seals remained within 100–200 m (328–656 ft) of the trackline as the operating airgun array passed by. Seal sighting rates at the water surface were lower during airgun array operations than during no-airgun periods in each survey year except 1997.

The operation of the airgun array had minor and variable effects on the behavior of seals visible at the surface within a few hundred meters of the array. The behavioral data indicated that some seals were more likely to swim away from the source vessel during periods of airgun operations and more likely to

swim towards or parallel to the vessel during non-seismic periods. No consistent relationship was observed between exposure to airgun noise and proportions of seals engaged in other recognizable behaviors, e.g. “looked” and “dove”. Such a relationship might have occurred if seals seek to reduce exposure to strong seismic pulses, given the reduced airgun noise levels close to the surface where “looking” occurs (Moulton and Lawson 2002).

In summary, visual monitoring from seismic vessels has shown only slight (if any) avoidance of airguns by pinnipeds, and only slight (if any) changes in behavior. These studies show that pinnipeds frequently do not avoid the area within a few hundred meters of an operating airgun array. However, initial telemetry work suggests that avoidance and other behavioral reactions may be stronger than evident to date from visual studies.

(f) Hearing Impairment and Other Physical Effects

Temporary or permanent hearing impairment is a possibility when marine mammals are exposed to very strong sounds, but there has been no specific documentation of this in the case of exposure to sounds from seismic surveys. Current NMFS policy regarding exposure of marine mammals to high-level sounds is that cetaceans and pinnipeds should not be exposed to impulsive sounds exceeding 180 and 190 dB re 1 μ Pa (rms), respectively (NMFS 2000). Those criteria have been used in establishing the safety (=shutdown) radii planned for numerous seismic surveys. However, those criteria were established before there was any information about the minimum received levels of sounds necessary to cause auditory impairment in marine mammals. As discussed below,

- the 180 dB criterion for cetaceans is probably quite precautionary, i.e., lower than necessary to avoid Temporary Threshold Shift (TTS) let alone permanent auditory injury, at least for delphinids.
- the minimum sound level necessary to cause permanent hearing impairment is higher, by a variable and generally unknown amount, than the level that induces barely-detectable TTS.
- the level associated with the onset of TTS is often considered to be a level below which there is no danger of permanent damage.

Several aspects of the monitoring and mitigation measures that are now often implemented during seismic survey projects are designed to detect marine mammals occurring near the airgun array, and to avoid exposing them to sound pulses that might cause hearing impairment. In addition, many cetaceans are likely to show some avoidance of the area with ongoing seismic operations (see above). In these cases, the avoidance responses of the animals themselves will reduce or avoid the possibility of hearing impairment.

Non-auditory physical effects may also occur in marine mammals exposed to strong underwater pulsed sound. Possible types of non-auditory physiological effects or injuries that might (in theory) occur include stress, neurological effects, bubble formation, resonance effects, and other types of organ or tissue damage. It is possible that some marine mammal species (i.e., beaked whales) may be especially susceptible to injury and/or stranding when exposed to strong pulsed sounds.

Temporary Threshold Shift (TTS)

TTS is the mildest form of hearing impairment that can occur during exposure to a strong sound (Kryter 1985). While experiencing TTS, the hearing threshold rises and a sound must be stronger in order to be heard. TTS can last from minutes or hours to (in cases of strong TTS) days. The magnitude of TTS

depends on the level and duration of noise exposure, among other considerations (Richardson et al. 1995). For sound exposures at or somewhat above the TTS threshold, hearing sensitivity recovers rapidly after exposure to the noise ends. Only a few data on sound levels and durations necessary to elicit mild TTS have been obtained for marine mammals, and none of the published data concern TTS elicited by exposure to multiple pulses of sound.

Toothed Whales.—Ridgway et al. (1997) and Schlundt et al. (2000) exposed bottlenose dolphins and beluga whales to single 1-s pulses of underwater sound. TTS generally became evident at received levels of 192 to 201 dB re 1 μ Pa rms at 3, 10, 20, and 75 kHz, with no strong relationship between frequency and onset of TTS across this range of frequencies. At 75 kHz, one dolphin exhibited TTS at 182 dB, and at 0.4 kHz, no dolphin or beluga exhibited TTS after exposure to levels up to 193 dB (Schlundt et al. 2000). There was no evidence of permanent hearing loss; all hearing thresholds returned to baseline values at the end of the study.

Finneran et al. (2000) exposed bottlenose dolphins and a beluga whale to single underwater pulses designed to generate sounds with pressure waveforms similar to those produced by distant underwater explosions. Pulses were of 5.1 to 13 milliseconds (ms) in duration and the measured frequency spectra showed a lack of energy below 1 kHz. Exposure to those impulses at a peak received SPL (sound pressure level) of 221 dB re 1 μ Pa produced no more than a slight and temporary reduction in hearing.

A similar study was conducted by Finneran et al. (2002) using an 80 in³ water gun, which generated impulses with higher peak pressures and total energy fluxes than used in the aforementioned study. Water gun impulses were expected to contain proportionally more energy at higher frequencies than airgun pulses (Hutchinson and Detrick 1984). “Masked TTS” (MTTS) was observed in a beluga after exposure to a single impulse with peak-to-peak pressure of 226 dB re 1 μ Pa, peak pressure of 160 kPa, and total energy flux of 186 dB re 1 μ Pa² · s. Thresholds returned to within 2 dB of pre-exposure value ~4 min after exposure. No MTTS was observed in a bottlenose dolphin exposed to one pulse with peak-to-peak pressure of 228 dB re 1 μ Pa, equivalent to peak pressure 207 kPa and total energy flux of 188 dB re 1 μ Pa² · s (Finneran et al. 2000, 2002). In this study, TTS was defined as occurring when there was a 6 dB or larger increase in post-exposure thresholds; the reference to masking (MTTS) refers to the fact that these measurements were obtained under conditions with substantial (but controlled) background noise. Pulse duration at the highest exposure levels, where MTTS became evident in the beluga, was typically 10–13 ms.

The data quoted above all concern exposure of small odontocetes to single pulses of duration 1 s or shorter, generally at frequencies higher than the predominant frequencies in airgun pulses. With single short pulses, the TTS threshold appears to be (to a first approximation) a function of the energy content of the pulse (Finneran et al. 2002). The degree to which this generalization holds for other types of signals is unclear (Nachtigall et al. 2003). In particular, additional data are needed in order to determine the received sound levels at which small odontocetes would start to incur TTS upon exposure to repeated, low-frequency pulses of airgun sound with variable received levels. Given the results of the aforementioned studies and a seismic pulse duration (as received at close range) of ~20 ms, the received level of a single seismic pulse might need to be on the order of 210 dB re 1 μ Pa rms (~221–226 dB pk-pk) in order to produce brief, mild TTS. Exposure to several seismic pulses at received levels near 200–205 dB (rms) might result in slight TTS in a small odontocete, assuming the TTS threshold is (to a first approximation) a function of the total received pulse energy. Seismic pulses with received levels of 200–205 dB or more are usually restricted to a radius of no more than 100 m (328 ft) around a seismic vessel.

Baleen Whales.—There are no data, direct or indirect, on levels or properties of sound that are required to induce TTS in any baleen whale.

Pinnipeds.—TTS thresholds for pinnipeds exposed to brief pulses (either single or multiple) have not been measured. Two California sea lions did not incur TTS when exposed to single brief pulses with received levels (rms) of ~178 and 183 dB re 1 μ Pa and total energy fluxes of 161 and 163 dB re 1 μ Pa²·s (Finneran et al. 2003). However, prolonged exposures show that some pinnipeds may incur TTS at somewhat lower received levels than do small odontocetes exposed for similar durations. For sounds of relatively long duration (20–22 min), Kastak et al. (1999) reported that they could induce mild TTS in California sea lions, harbor seals, and northern elephant seals by exposing them to underwater octave-band noise at frequencies in the 100–2000 Hz range. Mild TTS became evident when the received levels were 60–75 dB above the respective hearing thresholds, i.e., at received levels of about 135–150 dB. Three of the five subjects showed shifts of ~4.6–4.9 dB and all recovered to baseline hearing sensitivity within 24 hours of exposure. Schusterman et al. (2000) showed that TTS thresholds of these seals were somewhat lower when the animals were exposed to the sound for 40 min than for 20–22 min, confirming that there is a duration effect in pinnipeds. There are some indications that, for corresponding durations of sound, some pinnipeds may incur TTS at somewhat lower received levels than do small odontocetes (Kastak et al. 1999; Ketten et al. 2001; cf. Au et al. 2000).

Likelihood of Incurring TTS.—A marine mammal within a radius of ≤ 100 m (≤ 328 ft) around a typical array of operating airguns might be exposed to a few seismic pulses with levels of ≥ 205 dB, and possibly more pulses if the mammal moved with the seismic vessel.

As shown above, most cetaceans show some degree of avoidance of seismic vessels operating an airgun array. It is unlikely that these cetaceans would be exposed to airgun pulses at a sufficiently high level for a sufficiently long period to cause more than mild TTS, given the relative movement of the vessel and the marine mammal. However, TTS would be more likely in any odontocetes that bow-ride or otherwise linger near the airguns. While bow-riding, odontocetes would be at or above the surface, and thus not exposed to strong sound pulses given the pressure-release effect at the surface. However, bow-riding animals generally dive below the surface intermittently. If they did so while bow-riding near airguns, they would be exposed to strong sound pulses, possibly repeatedly. If some cetaceans did incur TTS through exposure to airgun sounds in this manner, this would very likely be a temporary and reversible phenomenon.

Some pinnipeds show avoidance reactions to airguns, but their avoidance reactions are not as strong or consistent as those of cetaceans (see above). Pinnipeds occasionally seem to be attracted to operating seismic vessels. As previously noted, there are no specific data on TTS thresholds of pinnipeds exposed to single or multiple low-frequency pulses. It is not known whether pinnipeds near operating seismic vessels, and especially those individuals that linger nearby, incur significant TTS.

NMFS (1995, 2000) concluded that cetaceans should not be exposed to pulsed underwater noise at received levels exceeding 180 dB re 1 μ Pa (rms). The corresponding limit for pinnipeds has been set at 190 dB. These sound levels are *not* considered to be the levels above which TTS might occur. Rather, they are the received levels above which, in the view of a panel of bioacoustics specialists convened by NMFS before TTS measurements for marine mammals started to become available, one could not be certain that there would be no injurious effects, auditory or otherwise, to marine mammals. As discussed above, TTS data that have subsequently become available imply that, at least for dolphins, TTS is unlikely to occur unless the dolphins are exposed to airgun pulses stronger than 180 dB re 1 μ Pa rms.

It has been shown that most large whales tend to avoid ships and associated seismic operations. In addition, ramping up airgun arrays, which is standard operational protocol for many seismic operators, should allow cetaceans to move away from the seismic source and to avoid being exposed to the full acoustic output of the airgun array. [Three species of baleen whales that have been exposed to pulses from single airguns showed avoidance (Malme et al. 1984–1988; Richardson et al. 1986; McCauley et al. 1998, 2000a,b). This strongly suggests that baleen whales will begin to move away during the initial stages of a ramp-up, when a single airgun is fired.] Thus, whales will likely not be exposed to high levels of airgun sounds. Likewise, any whales close to the trackline could move away before the sounds from the approaching seismic vessel become sufficiently strong for there to be any potential for TTS or other hearing impairment. Therefore, there is little potential for whales to be close enough to an airgun array to experience TTS. Furthermore, in the event that a few individual cetaceans did incur TTS through exposure to airgun sounds, this is a temporary and reversible phenomenon.

Permanent Threshold Shift (PTS)

When PTS occurs, there is physical damage to the sound receptors in the ear. In some cases, there can be total or partial deafness, while in other cases, the animal has an impaired ability to hear sounds in specific frequency ranges. Physical damage to a mammal's hearing apparatus can occur if it is exposed to sound impulses that have very high peak pressures, especially if they have very short rise times (time required for sound pulse to reach peak pressure from the baseline pressure). Such damage can result in a permanent decrease in functional sensitivity of the hearing system at some or all frequencies.

There is no specific evidence that exposure to pulses of airgun sound can cause PTS in any marine mammal. However, given the possibility that mammals close to an airgun array might incur TTS, there has been speculation about the possibility that some individuals occurring very close to airguns might incur TTS (Richardson et al. 1995, p. 372ff).

Single or occasional occurrences of mild TTS are not indicative of permanent auditory damage in terrestrial mammals. Relationships between TTS and PTS thresholds have not been studied in marine mammals but are assumed to be similar to those in humans and other terrestrial mammals. The low-to-moderate levels of TTS that have been induced in captive odontocetes and pinnipeds during recent controlled studies of TTS have been confirmed to be temporary, with no measurable residual PTS (Kastak et al. 1999; Schlundt et al. 2000; Finneran et al. 2002; Nachtigall et al. 2003). However, very prolonged exposure to sound strong enough to elicit TTS, or shorter-term exposure to sound levels well above the TTS threshold, can cause PTS, at least in terrestrial mammals (Kryter 1985). In terrestrial mammals, the received sound level from a single non-impulsive sound exposure must be far above the TTS threshold for any risk of permanent hearing damage (Kryter 1994; Richardson et al. 1995). For impulse sounds with very rapid rise times (e.g., those associated with explosions or gunfire), a received level not greatly in excess of the TTS threshold may start to elicit PTS. Rise times for airgun pulses are rapid, but less rapid than for explosions.

Some factors that contribute to onset of PTS, at least in terrestrial mammals, are as follows:

- exposure to single very intense sound,
- repetitive exposure to intense sounds that individually cause TTS but not PTS, and
- recurrent ear infections or (in captive animals) exposure to certain drugs.

Cavanagh (2000) has reviewed the thresholds used to define TTS and PTS. Based on this review and SACLANT (1998), it is reasonable to assume that PTS might occur at a received sound level 20 dB

or more above that inducing mild TTS. However, for PTS to occur at a received level only 20 dB above the TTS threshold, the animal probably would have to be exposed to a strong sound for an extended period, or to a strong sound with rather rapid rise time.

Sound impulse duration, peak amplitude, rise time, and number of pulses are the main factors thought to determine the onset and extent of PTS. Based on existing data, Ketten (1994) has noted that the criteria for differentiating the sound pressure levels that result in PTS (or TTS) are location and species-specific. PTS effects may also be influenced strongly by the health of the receiver's ear.

Given that marine mammals are unlikely to be exposed to received levels of seismic pulses that could cause TTS, it is highly unlikely that they would sustain permanent hearing impairment. If we assume that the TTS threshold for exposure to a series of seismic pulses may be on the order of 220 dB re 1 μ Pa (pk-pk) in odontocetes, then the PTS threshold might be as high as 240 dB re 1 μ Pa (pk-pk). In the units used by geophysicists, this is 10 bar-m. Such levels are found only in the immediate vicinity of the largest airguns (Richardson et al. 1995:137; Caldwell and Dragoset 2000). It is very unlikely that an odontocete would remain within a few meters of a large airgun for sufficiently long to incur PTS. The TTS (and thus PTS) thresholds of baleen whales and pinnipeds may be lower, and thus may extend to a somewhat greater distance. However, baleen whales generally avoid the immediate area around operating seismic vessels, so it is unlikely that a baleen whale could incur PTS from exposure to airgun pulses. Pinnipeds, on the other hand, often do not show strong avoidance of operating airguns.

Although it is unlikely that airgun operations during most seismic surveys would cause PTS in marine mammals, caution is warranted given the limited knowledge about noise-induced hearing damage in marine mammals, particularly baleen whales. Commonly-applied monitoring and mitigation measures, including visual monitoring, course alteration, ramp ups, and power downs or shut downs of the airguns when mammals are seen within the "safety radii", would minimize the already-low probability of exposure of marine mammals to sounds strong enough to induce PTS.

(g) Strandings and Mortality

Marine mammals close to underwater detonations of high explosive can be killed or severely injured, and the auditory organs are especially susceptible to injury (Ketten et al. 1993; Ketten 1995). Airgun pulses are less energetic and have slower rise times, and there is no proof that they can cause serious injury, death, or stranding. However, the association of mass strandings of beaked whales with naval exercises and, in a recent (2002) case, an L-DEO seismic survey, has raised the possibility that beaked whales may be especially susceptible to injury and/or behavioral reactions that can lead to stranding when exposed to strong pulsed sounds.

In March 2000, several beaked whales that had been exposed to repeated pulses from high intensity, mid-frequency military sonars stranded and died in the Providence Channels of the Bahamas Islands, and were subsequently found to have incurred cranial and ear damage (NOAA and USN 2001). Based on post-mortem analyses, it was concluded that an acoustic event caused hemorrhages in and near the auditory region of some beaked whales. These hemorrhages occurred before death. They would not necessarily have caused death or permanent hearing damage, but could have compromised hearing and navigational ability (NOAA and USN 2001). The researchers concluded that acoustic exposure caused this damage and triggered stranding, which resulted in overheating, cardiovascular collapse, and physiological shock that ultimately led to the death of the stranded beaked whales. During the event, five naval vessels used their AN/SQS-53C or -56 hull-mounted active sonars for a period of 16 h. The sonars produced narrow (<100 Hz) bandwidth signals at center frequencies of 2.6 and 3.3 kHz (-53C), and 6.8 to 8.2 kHz (-56). The

respective source levels were usually 235 and 223 dB re 1 μ Pa, but the -53C briefly operated at an unstated but substantially higher source level. The unusual bathymetry and constricted channel where the strandings occurred were conducive to channeling sound. This, and the extended operations by multiple sonars, apparently prevented escape of the animals to the open sea. In addition to the strandings, there are reports that beaked whales were no longer present in the Providence Channel region after the event, suggesting that other beaked whales either abandoned the area or perhaps died at sea (Balcomb and Claridge 2001).

Other strandings of beaked whales associated with operation of military sonars have also been reported (e.g., Simmonds and Lopez-Jurado 1991; Frantzis 1998). In these cases, it was not determined whether there were noise-induced injuries to the ears or other organs. Another stranding of beaked whales (15 whales) happened on 24–25 September 2002 in the Canary Islands, where naval maneuvers were taking place. A recent paper concerning the Canary Islands stranding concluded that cetaceans might be subject to decompression injury in some situations (Jepson et al. 2003). If so, this might occur if they ascend unusually quickly when exposed to aversive sounds. Previously it was widely assumed that diving marine mammals are not subject to the bends or air embolism.

It is important to note that seismic pulses and mid-frequency sonar pulses are quite different. Sounds produced by the types of airgun arrays used to profile sub-sea geological structures are broadband with most of the energy below 1 kHz. Typical military mid-frequency sonars operate at frequencies of 2 to 10 kHz, generally with a relatively narrow bandwidth at any one time (though the center frequency may change over time). Because seismic and sonar sounds have considerably different characteristics and duty cycles, it is not appropriate to assume that there is a direct connection between the effects of military sonar and seismic surveys on marine mammals. However, evidence that sonar pulses can, in special circumstances, lead to hearing damage and, indirectly, mortality suggests that caution is warranted when dealing with exposure of marine mammals to any high-intensity pulsed sound.

As discussed earlier, there has been a recent (Sept. 2002) stranding of two Cuvier's beaked whales in the Gulf of California (Mexico) when a seismic survey by the L-DEO/NSF vessel R/V *Maurice Ewing* was underway in the general area (Malakoff 2002). The airgun array in use during that project was the *Ewing's* 20-airgun 8490-in³ array. This might be a first indication that seismic surveys can have effects, at least on beaked whales, similar to the suspected effects of naval sonars. However, the evidence linking the Gulf of California strandings to the seismic surveys is inconclusive, and to this date is not based on any physical evidence (Hogarth 2002; Yoder 2002). The ship was also operating its multibeam bathymetric sonar at the same time but, as discussed elsewhere, this sonar had much less potential than the aforementioned naval sonars to affect beaked whales. Although the link between the Gulf of California strandings and the seismic (plus multibeam sonar) survey is inconclusive, this plus the various incidents involving beaked whale strandings "associated with" naval exercises suggests a need for caution in conducting seismic surveys in areas occupied by beaked whales.

(h) Non-auditory Physiological Effects

Possible types of non-auditory physiological effects or injuries that might theoretically occur in marine mammals exposed to strong underwater sound might include stress, neurological effects, bubble formation, resonance effects, and other types of organ or tissue damage. There is no proof that any of these effects occur in marine mammals exposed to sound from airgun arrays. However, there have been no direct studies of the potential for airgun pulses to elicit any of these effects. If any such effects do occur, they would probably be limited to unusual situations when animals might be exposed at close range for unusually long periods.

Long-term exposure to anthropogenic noise may have the potential of causing physiological stress that could affect the health of individual animals or their reproductive potential, which in turn could (theoretically) cause effects at the population level (Gisiner [ed.] 1999). However, there is essentially no information about the occurrence of noise-induced stress in marine mammals. Also, it is doubtful that any single marine mammal would be exposed to strong seismic sounds for sufficiently long that significant physiological stress would develop. This is particularly so in the case of seismic surveys where the tracklines are long and/or not closely spaced, as is the case for most two-dimensional seismic surveys.

Gas-filled structures in marine animals have an inherent fundamental resonance frequency. If stimulated at this frequency, the ensuing resonance could cause damage to the animal. There may also be a possibility that high sound levels could cause bubble formation in the blood of diving mammals that in turn could cause an air embolism, tissue separation, and high, localized pressure in nervous tissue (Gisiner [ed.] 1999; Houser et al. 2001). A recent workshop (Gentry [ed.] 2002) was held to discuss whether the stranding of beaked whales in the Bahamas in 2000 might have been related to air cavity resonance or bubble formation in tissues caused by exposure to noise from naval sonar. A panel of experts concluded that resonance in air-filled structures was not likely to have caused this stranding. Among other reasons, the air spaces in marine mammals are too large to be susceptible to resonant frequencies emitted by mid- or low-frequency sonar; lung tissue damage has not been observed in any mass, multi-species stranding of beaked whales; and the duration of sonar pings is likely too short to induce vibrations that could damage tissues (Gentry [ed.] 2002). Opinions were less conclusive about the possible role of gas (nitrogen) bubble formation/growth in the Bahamas stranding of beaked whales. Workshop participants did not rule out the possibility that bubble formation/growth played a role in the stranding and participants acknowledged that more research is needed in this area. The only available information on acoustically-mediated bubble growth in marine mammals is modeling assuming prolonged exposure to sound.

As noted in the preceding subsection, a recent paper (Jepson et al. 2003) has suggested that cetaceans can at times be subject to decompression sickness. If so, this could be another mechanism by which exposure to strong sounds could, indirectly, result in non-auditory injuries and perhaps death.

In summary, very little is known about the potential for seismic survey sounds to cause either auditory impairment or other non-auditory physical effects in marine mammals. Available data suggest that such effects, if they occur at all, would be limited to short distances. However, the available data do not allow for meaningful quantitative predictions of the numbers (if any) of marine mammals that might be affected in these ways. Marine mammals that show behavioral avoidance of seismic vessels, including most baleen whales, some odontocetes, and some pinnipeds, are unlikely to incur auditory impairment or other physical effects.

Literature Cited

Literature mentioned in this Appendix is listed in the overall Literature Cited section earlier in this document.